

**GREENFIELD 2023-CCMG
GREENFIELD, IN
ADDENDUM #1**

Date: February 3, 2023

To All Plan Holders:

The following items have been included:

1. Meeting Minutes from Pre-Bid Meeting held on 1/30/2023 including Q&A

Please acknowledge receipt of this addenda in Part 4 of the Bid Package.

PRE-BID MEETING AGENDA

Date: January 30, 2023
Time: 2:00pm
Location: Larry Breese Conference Room, City Hall
Subject: **Greenfield 2023-CCMG Resurfacing Bid (Des. No. 2201395)**
Participants: **See sign-in sheet**

I. Introductions

- a. Owner: City of Greenfield
Tyler Rankins (317) 477-4380
- b. Engineer: Jason Koch, City Engineer (317) 325-1322

II. Project Description

A. Contract Book Review

- i. Scope of Work Mill 1.5” and resurface with 2” of HMA Surface, Type B, 12.5mm with associated pavement markings and ADA ramp replacements where necessary. MOT and construction engineering is not itemized and should be included in the cost of other items.
- ii. Bid Tabulation: Lump Sum (Schedule of values for invoicing/change orders)
- iii. Bid Opening: February 14, 2023 at 10:00am (**bids due by 9:30am at Clerk-Treasurer’s Office, 10 S. State Street, Greenfield, IN**)

BID PACKET REQUIREMENTS

- a. PART 1: Bidder Info
- b. PART 2: Bid Price
- c. PART 3: Schedule of Values
- d. PART 4: Addenda Acknowledgement
- e. PART 5: Exceptions
- f. PART 6: Nepotism Disclosures
- g. PART 7: Additional Declarations (*Apprentice Program, Drug Testing program, Contractor Prequalification requirements*)
- h. PART 8: Drug Plan
- i. PART 9: Non-Collusion Affidavit
- j. PART 10: E-Verify Program
- k. PART 11: Notarized Signatures
- l. Form 96 (Financial Statement)
- m. Bid Bond

- iv. Proposal Schedule: Anticipated award date – March 14, 2023
Anticipated NTP – April 1, 2023
Substantial Completion – November 3, 2023
Final Completion – December 18, 2023
- v. Liquidated Damages \$500/day for Substantial Completion
\$100/day for Final Completion
- vi. General Conditions <https://www.greenfieldin.org/government/engineering>
Incorporated by reference

B. Special Provision and Drawings Review

C. Addendum Items

- i. Addendum No. 1 will be uploaded by February 3, 2023 by 4:00 p.m. and will include the pre-bid meeting minutes and answers to any pre-bid questions.
- ii. Last chance for additional questions will be February 1, 2023 at noon.

VII. Miscellaneous

- a. Please provide all questions and comments to Jason Koch, City Engineer, jkoch@greenfieldin.org or (317) 325-1322.
- b. Contractors are to inform themselves of the existing site conditions.
- c. Contractors are to coordinate material storage site and accessing work.
- d. Contractors are to coordinate with all utilities

VII. Questions

Q: At what point does Greenfield want the base repair completed, before or after milling?
A: Base repairs should be completed prior to surface milling at the direction of the Street Department.

Q: Are the base repair areas marked? If not, do you have a patch count per street or is your quantity based on a percentage

A: No, base repair areas will be determined by the Street Department at a pre-construction meeting with the Contractor. The estimate of base repair per street segment can be found on the last page of the technical specs in the contract book – all quantity estimates are broken down per street segment, including base repair.

Q: Will the patches require saw cutting in addition to the milled edge?

A: No

Q: Is joint sealant and joint adhesive required and if so will you be issuing an addendum capturing same?

A: No

Q: There is no quantity for inlet adjustments at ADA ramps, specifically on the south end of the Riverview Dr segment. How do we handle that?

A: City forces will made the adjustments prior to, or in conjunction with, the project to avoid conflicts with ADA ramps

Q: There is no pay item for curb removal. How do you want to handle that?

A: The cost of curb removals should be included in the cost of sidewalk removal.

CCMG-2023-1 Pre-Bid Mtg

1/30/2023

<u>Name</u>	<u>Org</u>	<u>Email</u>
Jason Ketch	Greenfield Eng	jkock@greenfieldin.org
Shawz PETERS	CROSSROADS AGG	JPETERS@WM.COM
Tyler Rankins	Greenfield Street	trankins@greenfieldin.org
CAM PADDOCK	EiB PAVING	cam.paddock@ebpaving.com
Mike Shelley	EiB Paving	mike.shelley@ebpaving.com
Brod Evans	Greenfield Street	bevens@greenfieldin.org
ARON ROBERTSON	Robertson Paving	aron@robertsonpaving.com
Keeton Cooper	Rieth-Biley	kcooper@rieth-riley.com